

नोटीस

विषय : विकास प्राधिकरण पेठ क्र. 12 येथील प्रस्तावित गृहयोजनेकरीता उभारावयाच्या सबस्टेशनचे अंदाजपत्रक बनविणेकरीता दरपत्रके सादर करणेबाबत

विकास प्राधिकरणामार्फत पेठ क्र. 12 येथे गृहयोजना उभारण्याचे काम प्रस्तावित आहे. सदरच्या गृहयोजनेकरीता 20 MVA, 22/11 क्षमतेचे सबस्टेशन उभारणे प्रस्तावित आहे. सदरचे सबस्टेशन उभारणीचे कामाकरीता खालीलप्रमाणे विद्युत विषयक बाबींचे दरपत्रके मागविण्यात येत आहेत.

Sr. No.	Item Description	Qty
1	Supplying, installing, testing and commissioning FR, XLPE armoured cable 19 core 2.5 sq.mm. copper conductor complete erected on wall/ ceiling complete as per specification no. CBLT/CU	800.00
2	Supply installation testing commissioning of MSEDCL approved 22 KV 3 P Mechanically Gang Operated Circuit Breaker along with support Structure 24 KV,1600A,SC rating 25KA/3 Sec as per MSEDCL Guidelines	2.00
3	Supply installation testing commissioning of MSEDCL approved 22 KV Isolator with Earth Switch along with insulator & support structure. 24 KV,800A,SC rating 25 KA/3 sec creepage distance 900 mm,4KN	2.00
4	Supply installation testing commissioning of MSEDCL approved 22 KV Isolator without Earth Switch along with insulator & support structure. 24 KV,800A,SC rating 25 KA/3 sec creepage distance 900 mm,4KN	2.00
5	Supply installation testing commissioning of MSEDCL approved 22KV Current Transformer for feeder bay24 KV,400-200/1A,3 Core, SC rating , 25 KA/3sec.	6.00
6	Supply installation testing commissioning of MSEDCL approved 22 KV Lighting Arresters, with cable support structure along with mouting arrangement of LA Gurantry Structure mounted along with power connecter 18 KV,10KA, Station class	8.00
7	Supply installation testing commissioning of MSEDCL approved 22 KV feeder control & protection panels Double feeder panel with numerical Type	2.00
8	Supply installation testing commissioning of MSEDCL approved Equipment Support Structure & nut bolts including the foundation bolts for Bay	0.80
9	Supply installation testing commissioning of MSEDCL approved 110mm Dia. Rigid PVC Pipe conforming to IS 13952 & of pressure 4kg/sq.Cm along with necessary fittings conforming to IS 14735 amended upto date	50.00
10	Supply installation testing commissioning of MSEDCL approved Palms for CB (C18) Alluminium, 4 holes Comp type suitable for 0.4Z as per MSEDCL Guidelines	12.00
11	Supply installation testing commissioning of MSEDCL approved 0.4 ACSR Zebra Conductor for Bay work	180.00

12	Supply installation testing commissioning of MSEDCL approved 22 Kv Jumping work	12.00
13	Supply installation testing commissioning of MSEDCL approved Stud Single (C10b) for CT/PT Electrolytic Copper Comp Type suitable for 0.4Z as directed by MSEDCL Authority	12.00
14	Supply installation testing commissioning of MSEDCL approved Palm type Clamp for Isolator (C15) suitable for suitable for 0.4Z Conductor.	24.00
15	Supply installation testing commissioning of MSEDCL approved 60 Terminals CT MB including necessary testing of same by MSEDCL.	2.00
16	Supply installation testing commissioning of MSEDCL approved with necessary material required as per directions of MSEDCL for Grounding of CT MB	2.00
17	Supply installation testing commissioning of MSEDCL approved .4Z "T" connector Twin to single as per requirements & guidelines by MSEDCL authority	6.00
18	Supply installation testing commissioning of MSEDCL approved 80X80X2mm Bimetalic plate with necessary fitting as per direction of MSEDCL	6.00

विषयांकीत विद्युत विषयक बाबींचे दरपत्रक आपल्या लेटरहेडवर कार्यकारी अभियंता (विद्युत) यांचे कार्यालयात दिनांक 06/02/2019 पर्यंत दुपारी 1:00 वाजेपर्यंत आणून द्यावे, आपले दरपत्रक वाहतूक, व इतर सर्व करांसहीत असावेत.(GST वगळून) सदरचे दरपत्रक फ्रक्त अंदाजपत्रक तयार करणेसाठी वापरण्यात येणार आहे, तसेच या दरपत्रकावर कोणतेही काम अदा होणार नाही याची संबंधितांनी नोंद घ्यावी.

sd/--

कार्यकारी अभियंता
विद्युत विभाग